Ref: 90-129701-049

June 8, 2006

Mr. Robert Stone Humboldt County Department of Health and Human Services Division of Environmental Health 100 H Street, Suite 100 Eureka, CA 95501

Re: Groundwater Monitoring Data for April 2006

Former Dutra Trucking, 5005 Boyd Road, Arcata, California

LOP # 12264

Dear Mr. Stone:

On behalf of Mr. Frank Dutra, Winzler & Kelly Consulting Engineers (Winzler & Kelly) is submitting this report of groundwater monitoring data collected in April 2006 for the above-referenced site.

The purpose of this report is to document the activities, results, and findings of the periodic groundwater monitoring program. All figures and tables referred to herein are included in Appendix A and Appendix B, respectively. Laboratory analytical reports are contained in Appendix C, Standard Operating Procedures (SOPs) are contained in Appendix D, and field notes are contained in Appendix E.

#### **Groundwater Monitoring Activities**

On April 26 and 27, 2006, a Winzler & Kelly geologist obtained water levels from the five site monitoring wells following a period of very heavy rainfall. Monitoring well, MW-4, contained inadequate water for sampling. Monitoring well MW-1 was not purged prior to sampling due to minimal water present in the well. Monitoring wells MW-2, MW-3 and MW-5 were purged and sampled according to Winzler & Kelly SOPs for *Monitoring Well Purging and Sampling Activities* (Appendix D). The on-site production well was gaged for depth to groundwater and total depth of the well. Site vicinity, monitoring well locations, and previous groundwater gradient information are shown on Figures 1, and 2, respectively (Appendix A).

#### Aquifer Data

Depth to water measurements were collected after removing well caps and allowing groundwater to stabilize for at least 15 minutes. No pressure was noted upon opening any the wells. Cumulative water level measurements are presented in Table 1 (Appendix B). Hydrologic analyses are



calculated from surveyed well positions and casing elevations and measured depth to water data in accordance with Winzler & Kelly SOPs (Appendix D).

Ontiveros & Associates surveyed the well locations and top of well elevations on March 3, 2004. Top of casing elevations were surveyed to the nearest 0.01 foot above mean sea level (msl) relative to the NAD88 datum, as required for submittal of survey data to the State Water Resource Control Board Geotracker System (Geotracker). Well locations were surveyed relative to the State Plane Coordinate System and in degrees latitude/ longitude to seven decimal places. Cumulative aquifer data are presented on Tables 1 and 2, (Appendix B). These survey data and periodic groundwater calculations are electronically submitted the Geotracker database.

Across the approximately 100 feet between monitoring wells at this site, measured groundwater elevation differed by approximately 15 feet on April 26, 2006. Per our April 2006 calculations, groundwater gradient was approximately 23 feet per 100 feet along the gradient direction. As the former Dutra Trucking site is a nearly flat floodplain, these groundwater data appear to indicate that a perched condition is present below part of the site, to explain the calculated steep groundwater gradients.

#### **Groundwater Sampling**

On April 26 and 27 2006, monitoring well MW-2, MW-3 and MW-5 were purged and sampled in accordance with Winzler & Kelly Standard Operating Procedures (Appendix D). All monitoring well sampling was performed after removing three wetted casing volumes of water from the wells and allowing the water levels to recover to at least 80% of its pre-purge level. Monitoring well MW-1 was sampled without purging due to anticipated slow recharge. Monitoring well MW-4 was not sampled due to insufficient water in well to enter sampling bailer. Monitoring well MW-5 was sampled approximately 12 hours after purging due to slow recharge.

As part of the quarterly monitoring program, groundwater samples collected from the site monitoring wells were analyzed for the following:

 Total Petroleum Hydrocarbons as Diesel (TPH-D) by EPA Method 3550; silica gel cleanup and retesting for TPH-D was performed on samples producing detectable results.

#### **Groundwater Analytical Results**

Groundwater samples collected from wells outside of the former UST excavation produced no detectable TPH-D contaminants for the April 2006 sampling event. In April 2006, groundwater within the excavation (MW-3) produced TPH-D at 1500 parts per billion (ppb) before silica gel cleanup and 58 ppb following silica gel cleanup.



Laboratory analytical results and this full report will be submitted electronically to the State Water Resources Control Board (SWRCB) Geotracker System. Cumulative laboratory analytical results are presented in Table 3 (Appendix B). A copy of the current laboratory analytical report is included in Appendix C.

#### Quality Assurance/Quality Control (QA/QC)

Field QA/QC was provided by adherence to the Winzler & Kelly Standard Operating Procedures for "Monitor Well Purging and Sampling Activities", contained in Appendix D.

Laboratory QA/QC was provided by the use of lab Method Blanks to preclude false positive analysis of analytes and the use of Laboratory Control Spike (LCS) and Laboratory Control Spike Duplicate (LCSD) samples to evaluate the percentage recovery of target analytes and reproducibility during analysis.

The laboratory provided the following notes regarding QA/QC:

"THIS IS AN AMENDED REPORT. The diesel result prior to silica gel cleanup was added per client's request.

All samples submitted for silica gel cleanup were initially analyzed for diesel. The samples showing no detectable levels of the analyte were not subjected to the cleanup procedure.

TPH as Diesel w/ Silica Gel Cleanup: Sample MW-3 contains material similar to degraded or weathered diesel oil.

The Laboratory Control Sample Duplicate (LCSD) recovery as below the lower acceptance limit for diesel. The Laboratory Control Sample (LCS) recovery was within the acceptance limits; therefore the data were accepted.

TPH as Diesel

The low surrogate recovery for sample MW-1 may be due to the sample matrix."

#### Discussion

Groundwater gradient was calculated to flow to the northwest (288 degrees) in April 2006 at 22.87 feet per 100 feet. These calculated data are suspect and are likely an artifact of (1) multiple aquifers being tapped on different portions of the site or (2) recharge of groundwater to some wells from a source other than the regional unconfined aquifer.



Groundwater quality as sampled from monitoring wells outside of the former UST excavation produced no detectable TPH-D contaminants for the April 2006 sampling event. In April 2006, groundwater within the excavation (MW-3) produced TPH-D at 1500 ppb before silica gel cleanup and 58 ppb following silica gel cleanup. If a similar decrease in TPH-D concentrations is realized during the July 2006 sampling event, a request will be made to recommend this site for regulatory closure.

#### Conclusions

- In April 2006, monitoring wells located outside of the former UST excavation produced no detectable concentrations of TPH as diesel.
- In April 2006, monitoring well MW-3 located within the former UST excavation produced widely variable results for TPH as diesel with silica gel cleanup (58 ppb) and without silica gel cleanup (1500 ppb).
- The April 2006 groundwater sampling event encountered groundwater in all five site wells. Four of the five wells produced adequate groundwater for sampling.
- A production well north of the monitoring well field was gaged indicating that the piezometric surface of the local aquifer is 25.7 feet below the ground surface. This depth to static groundwater is in keeping with the gage data recorded from the deeper monitoring wells MW-1, MW-4, and MW-5.
- Groundwater elevation and contaminant data appear to indicate that groundwater in the former UST pit and along the eastern side of the former UST excavation is perched, possibly receiving recharge water from a freeway drainage pipe.
- Compact, fine-grained soils and a perched unconfined aquifer appear to restrict the migration of residual diesel contamination in groundwater to the confines of the former tank excavation.
- The next groundwater sampling event is scheduled for July 2006.

#### Recommendations

- In April 2006, groundwater from monitoring well MW-3, located within the former UST excavation, produced TPH-D at 1500 ppb before silica gel cleanup and 58 ppb following silica gel cleanup. If a similar decrease in TPH-D concentrations is found following silica gel cleanup during the July 2006 sampling event, a request will be made to recommend this site for regulatory closure.
- If the July 2006 sampling event does not provide a contrast of TPH-D results before and after silica gel cleanup, Winzler & Kelly will schedule a limited subsurface investigation to investigate if the shallow aquifer is draining to a deeper aquifer via the 25 foot monitoring wells. This work has been requested by the HCDEH. This request will require the installation of two 15 foot well points or shallow wells



approximately midway between existing monitoring wells MW-1 and MW-4 as well as between MW-4 and MW-5.

If you have any questions or comments, please do not hesitate to call.

Sincerely,

WINZLER & KELLY

Kenneth Thiessen, CEG #2224 Geologist

GCO

tc

Enclosures: A

Appendix A: Figures

Figure 1 Site Vicinity Map Figure 2 Gradient Site Map

Appendix B: Tables

Table 1 Groundwater Level Measurements

Table 2 Groundwater Gradient Data Table 3 Groundwater Analytical Results Appendix C: Laboratory Analytical Reports Appendix D: Standard Operating Procedures

Appendix E: Field Notes

#### Distribution list:


Mr. Frank Dutra P.O. Box 898 Willow Creek, California 95573


Mr. Robert Stone Humboldt County Department of Public Health Division of Environmental Health 100 H Street, Suite 100 Eureka, California 95501 Winzler & Kelly

Fax:7074448330

Jun 8 2006 16:28

P.06





## TABLE 1 WATER TABLE ELEVATION MEASUREMENTS Former Dutra Trucking, LOP #12264

				A	B	(A-B=C)	D	Δ-Ω
	·	Groundwater	Top of	Depth to	Depth to	Product	Correction	Equivalent Depth
Well	Date	Elevation	Casing	Water	Product	Thickness	Factor	to Water
Number		(11)	(£)	(#)	(ft)	(ft)	(C x 0.729*)	Œ
	4-Feb-04	33.48	48.03	14,55	0.00	0.00	00'0	14.55
	3-May-04	DRY	48.03	DRY	DRY	DRY	DRY	DRY
MW-1	30-Nov-04	DRY	48.03	DRY	DRY	DRY	DRY	DRY
	4-Mar-05	DRY	48.03	DRY	DRY	DRY	DRY	DRY
	5-Jul-05	DRY	48.03	DRY	DRY	DAY	DRY	DRY
	26-Apr-06	27.37	48.03	20.66	00.0	0.00	0.00	20.66
	4-Feb-04	39.94	47.49	7.55	00.0	00:00	0.00	7.55
	3-May-04	34.49	47.49	13.00	0.00	0.00	00.0	13.00
MW-2	30-Nov-04	33.96	47.49	13.53	0.00	00.0	00.00	13.53
· · · · ·	4-Mar-05	39.83	47.49	7.66	0.00	00.0	00.00	7.66
	5-Jul-05	33.20	47.49	14.29	00.0	00.0	0.00	14.29
	26-Apr-06	38.74	47.49	8.75	0.00	00.00	00.00	8.75
	4-Feb-04	37.49	47.80	10.31	00:00	00:0	00.0	10.31
	3-May-04	35.35	47.80	12.45	00.0	00.0	0.00	12.45
MW-3	30-Nov-04	33,39	47.80	14.41	00.0	00.00	0.00	14.41
1	4-Mar-05	36.05	47.80	11.75	00.0	0.00	0.00	11.75
	5-Jul-05	35.40	47.80	12.40	00.0	0.00	0.00	12.40
	26-Apr-06	36.96	47.80	10.84	0.00	0.00	0.00	10.84
	4-Feb-04	DRY	48.54	DRY	DRY	DRY	DRY	DRY
1	3-May-04	DHY	48.54	DRY	DRY	DRY	DRY	DRY
MW-4	30-Nov-04	DRY	48.54	DRY	DRY	DRY	DRY	DRY
	4-Mar-05	DRY	48.54	DRY	DRY	DRY	DRY	DRY
	5-Jul-05	DRY	48.54	DRY	DRY	DRY	DRY	DRY
5.	26-Apr-06	23.96	48.54	24.58	0.00	0.00	00.0	24.58
	4-Feb-04	40.06	48.62	8.56	0.00	00.00	0.00	8.56
	3-May-04	30.17	48.62	18.45	0.00	0.00	0.00	18.45
MW-5	30-Nov-04	DRY	48.62	DRY	DRY	DRY	DRY	DRY
	4-Mar-05	38.52	48.62	10.10	0.00	0.00	0.00	10.10
	5-Jul-05	30.37	48.62	18.25	0.00	0.00	0.00	18.25
	26-Apr-06	37.45	48.62	11.17	0.00	0.00	0.00	11.17

\*0.729 is the density of gasoline at 15oC as referenced in the API Publication 1628, Second Edition, August, 1989 NA Not applicable

	Gradient	Gradient
Date	Direction	Magnitude
	(degrees Azimuth)	(ft./100 ft.)
1/29/2002 *	Northwest (293.5)	10.3
2/04/2004 **	West (271)	12.53
5/03/2004 **	Northeast (71)	16
11/30/2004****	Insufficient data	Insufficient data
3/4/2005**	West (278)	20.6
4/26/2006	Northwest (288)	22.87

\* Gradient direction and magnitude based upon gage data from soil borings; not a product of survey.

\*\* Gradient direction and magnitude based upon permanent monitoring well locations and survey information.

\*\*\*\* Gradient direction and magnitude could not be calculated due to lack of water in three of the five wells.

TABLE 3
GROUNDWATER ANALYTICAL RESULTS
Former Dutra Trucking, LOP #12264 (All units reported in parts per billion)

Sample Date	· ·		-											_				
SUBSURFACE INVESTIGATION JAN.	TPH as Diesel	TPH as Motor 1	TPH as Gasoline	Benzene	Toluene	Ethyl- benzene	10	(MTBE) Methyl Tertlary Butyl Ether	므로	(ETBE) Ethyl Tertlary Butyl Ether	(TAME) Tertlary Amyl Methyl	(TBA) Tertiary Butyl Alcohol	(1,2 DCB) 1,2. Dichloro benzene	(1,3 DCB) 1,3- Dichloro benzene	(1,4 DCB) 1,4. Dichiora	(1,2 DCA) 1,2- Dichloro	(EDB) 1,2 Dibromo	Š
		-   8	7999	Taka I	Legal Transfer	Tadal .	The state of the s	(DBD)	Todal	(ppb)	Ether (ppb)	(qdd)	(qdd)		(qdd)	(ppp)	(pbp)	: Chioro Ibenzene (nob)
28-Jan-02		ND ON	ON	ON	QN	ON	QN	QN	CN	S	GN	FILE						
28-Jan-02	QN	ΩN	Q	Q	ON	Q	Q	Q	S	Ş				2	S	DD	QN	S
29~Jan-02	180	S	Q	민	S	2	9	Q	S	2	2		200	9	Q	Q	S	9
29-Jen-02	- 5	QN	2	QN	2	2	2	Q	QN	5	AID.	CIV		2	3	2	Q	2
29-Jan-02	7	2	9	QV	2	Q	Q	GN	QN.	S	2	22	2 2	2	2	Q	QN	QN
30-Dec-02	21,000	6,500	22	22	22	99	25	22	22	2	2	202	22	22	22	25	22	9
CIECUTOR OF	1001	. 000 1			*		Ch.		THE STATE OF THE S	NO.	NO	QN	QV	QN	S S	2	1	
MVV-1 4-Feb-04 NO FEB 2004 MONITORING	E CN	2 2004 MC	N TORIN	GEVENT	LIV.	CIN									* The second of the last of th			25
TO THE STATE OF	2 2		2 4	CIN.	2	2	Q .	QN	Q	QN	QΝ	QN	NA	NA	NA	MA	4,1	
4-Feb-04	35	25	2 2	2	9	Q S	9 9	2	Q	QN	QN	ON.	MA	AN	AM	¥ 5	NA:	NA
4-Eab-04	700	2	2		2	2	2	Q.	9	QV	£	QN	NA	NA	N N	Y V	Z Z	NA
4-Fah-04	5 5	CIN CIN	S	CZ	-						-					5	<u> </u>	NA.
				- I		INC.		ND ON	QN .	S.	NO	QN	NA	A	NA	VV	914	
MAY 2004 GROUNDWATER MONITORING EVENT	NITORIN	3 EVENT													-		THE STATE OF THE S	NA
3-May-04	DRY		-		***************************************													
3-May-04	Q.	NA	NA	QN	ĊZ	GN	CN	CIN	VIV	414								
3-May-04	850	NA	NA	QN	2	- CN	2 5	2 9	S VIV	NA	YN.	AN	NA	NA	NA	NA	NA	VIV
3-May-04	DRY								Ş	T.	NA	FIA	NA	NA	NA	NA	ΝΑ	NA NA
3-May-04	Q.	NA	NA	QN	ΔN	e S	Q.	QN	NA	AN	NA	MA	P. I.					
NOVEMBER 2004 GROUNDWATER MONITORING EVENT	TER MON	TORINGE	VENT							Berlindade Franchistorio (Williamon a sa Albo).	Thirte managed to the party of the state of	1000	130	NA	NA	NA	NA	NA
30-Nov-04	YRO						1											
30-Nov-04	2	NA	NA	CN	- CN	ND CN	NS.	A P	614							·		
	9 500	-	\$ 12 2						- N	NA.	NA	¥	NA	NA	NA	AM	¥	NA
_	740	1/1/1	<u> </u>	Į.	2	ND ND	2	ON ON	NA	NA	NA	NA	NA	NA	NA	ΔN.	VIV.	
	DRY																5	XV.
MABCH 2005 GROUNDWATER MONITORING EVENT	GOTINON	ING EVEN	_			And the second second second second		***************************************	(All) chalements are reconsisted to the									
4-Mar.05	Var		-		-	The state of the s												
-		1	NA	MO	dN	CZ	ç									_	-	
ļ.,	_	NA	NA.	S	2 5	2 5	2 5	22	Y Y	NA.	V.	ΨM	άN	NA	NA	NA	NA	VIV
H	DRY						2	D.	VIII.	NA	NA	MA	NA	NA	NA	NA	NA	Z P
4-Mar-05	QN QN	NA	ΑA	QN.	GN	Q.	GN	ND I	NA	NA	ЫA	NA	NA	AN	NA	MA	VIV	
ABBII 2006 CBOHNDWATER MONTOONIC	MIGOTINO	TMB/G C															<u> </u>	Į.
00 00		L C C V II V				-	-			***************************************								***
1	+	+	¥ S	NA Na	NA	¥:	NA	NA	NA	ΝΑ	NA	AA	NA	VIA	VIA.	ŀ		
27-Apr-06 15	1500/58*	NA AM	NA N	AN V	NA NA	NA NA	NA.	¥.	¥:	NA	NA	NA	NA	NA	NA NA	+	NA	M.
•	_	1	N.A.	NA	NA.	NA.	NA	-NA	NA	MA	NA	NA	NA	NA.	NA	NA NA	NA	ď.
1	ļ	NIA	MA	MA	414											+	NA	NA
4		-	W.	NA	N.A.	NA	NA	NA	NA	NA	NA	NA	NA	MA	NIA			

\*TPH-D results with and without silica gel cleanup

ND Not Detected NA Not Analyzed DRY no water in well

1 of 1

Winzler & Kelly

Fax:7074448330

Jun 8 2006 16:28

P. 12



May 24, 2006

Winzler and Kelly 633 Third Street Eureka, CA 95501

Attn: Ken Thiessen

RE: 90129701-049/Dutra Trucking

#### SAMPLE IDENTIFICATION

Fraction	Client Sample Description	
01A	MW-1	-
02A	MW-2	
03B	MW-3	
04A	MW-5	

Order No.:

0604525

Invoice No.: 58077

PO No.:

ELAP No. 1247-Expires July 2006

ND = Not Detected at the Reporting Limit

Limit = Reporting Limit

All solid results are expressed on a wetweight basis unless otherwise noted.

REPORT CERTIFIED BY

Laboratory Supervisor(s)

QA Unit

Jesse G. Chaney, Jr. Laboratory Director North Coast Laboratories, Ltd.

Date: 24-May-06

CLIENT:

Winzler and Kelly

Project:

90129701-049/Dutra Trucking

Lab Order:

0604525

CASE NARRATIVE

#### THIS IS AN AMENDED REPORT.

The diesel result prior to silica gel cleanup was added per clients request.

All samples submitted for a silica gel cleanup were initially analyzed for diesel. The samples showing no detectable levels of the analyte were not subjected to the cleanup procedure.

TPH as Diesel w/ Silica Gel Cleanup:

Sample MW-3 contains material similar to degraded or weathered diesel oil.

The laboratory control sample duplicate (LCSD) recovery was below the lower acceptance limit for diesel. The laboratory control sample (LCS) recovery was within the acceptance limits; therefore, the data were accepted.

#### TPH as Diesel:

The low surrogate recovery for sample MW-1 may be due to the sample matrix.

Date:

24-May-06

WorkOrder: 0604525

ANALYTICAL REPORT

Client Sample ID: MW-1

Lab ID: 0604525-01A

Received: 4/27/06

Collected: 4/26/06 16:30

Test Name: TPH as Diesel

Reference: EPA 3510/GCFID(LUFT)/EPA 8015B

<u>Parameter</u>	Result	Limit	<u>Units</u>	DF	Extracted	Analyzed
TPHC Diesel (C12-C22) Surrogate: N-Tricosane	ND	50	μg/L	1.0	5/2/06	5/3/06
	8.88	70-130	% Rec	1.0	5/2/06	5/3/06

Client Sample ID: MW-2

Lab ID: 0604525-02A

Received: 4/27/06

Collected: 4/27/06 15:05

Test Name: TPH as Diesel

Reference: EPA 3510/GCFID(LUFT)/EPA 8015B

<u>Parameter</u>	Result	<u>Limit</u>	<u>Units</u>	DF	Extracted	Analyzed
TPHC Diesel (C12-C22)	ND	50	μg/L	1.0	5/2/06	5/3/06
Surrogate: N-Tricosane	72.1	70-130	% Rec	1.0	5/2/06	5/3/06

Client Sample ID: MW-3

Lab ID: 0604525-03B

Received: 4/27/06

Collected: 4/27/06 15:15

Test Name: TPH as Diesel

Reference: EPA 3510/GCFID(LUFT)/EPA 8015B

<u>Parameter</u>	Result	Limit	Units	$\mathbf{DF}$	Extracted	Analyzed
TPHC Diesel (C12-C22)	1,500	500	µg/L	10	5/2/06	5/3/06
Surrogate: N-Tricosane	77.0	70-130	% Rec	10	5/2/06	5/3/06

Test Name: TPH as Diesel with Silica Gel Cleanup

Reference: EPA 3510/3630/GCFID(LUFT)/8015B

Parameter	Result	<u>Limit</u>	Units	$\underline{\mathbf{DF}}$	Extracted	Analyzed
TPHC Diesel (C12-C22)	58	50	μg/L	1.0	5/7/06	5/10/06
Surrogate: N-Tricosane	39.7	38-129	% Rec	1.0	5/7/06	5/10/06
	•				The second second	

Client Sample ID: MW-5

Received: 4/27/06

Collected: 4/27/06 14:55

**Lab ID:** 0604525-04A

Test Name: TPH as Diesel

Reference: EPA 3510/GCFID(LUFT)/EPA 8015B

<u>Parameter</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	$\underline{\mathbf{DF}}$	<b>Extracted</b>	<u>Analyzed</u>
TPHC Diesel (C12-C22)	ND	50	μg/L.	1.0	5/2/06	5/3/06
Surrogate: N-Tricosane	76.2	70-130	% Rec	1.0	5/2/06	5/3/06
••						

B - Analyte detected in the associated Method Blank

Ltd.
ories,
boratories
Coast La
_
North

Date: 24-May-06

CLIENT: Win Work Order: 0602 Project: 9012	Winzler and Kelly 0604525 90129701-049/Dutra Trucking						OCSE	QC SUMMARY REPORT Method Blank	ORT Blamk
Sample ID MB-15656 Client ID:	Batch ID: 15656	Test Code; Run ID:	Test Code: SGTPHDW Un Run ID: ORGC5_060510A	Units: µg/L 10A	TOTAL STATEMENT OF THE	Analysis SeqNo:	Analysis Date 5/10/06 2:13:13 PM SeqNo: 591461	Prep Date 5/7/06	Carporation (Management
Analyte .	Result	Limit	SPK value SPK Ref Val	SPK Ref Val	% Rec	LowLimit	% Rec LowLimit HighLimit RPD Ref Val	%RPD RPDLimit	Qual
TPHC Diesel (C12-C22) N-Tricosane	ND 24.7	50	. 50.0	0	49.5%	88	129 0		777
Sample ID MB-15630 Client ID:	Batch ID: 15630	Test Code: Run ID:	Code: TPHDIW Units: µg/L ID: ORGC7_060503A	Units: µg/L 33A	VIORATE TOTAL STATES OF THE ST	Analysis SeqNo:	Analysis Date 5/3/06 2:24:20 PM SeqNo: 590267	Prep Date <i>5/2/</i> 06	
Analyfe	Result	Limit	Limit. SPK value SPK Ref Val	SPK Ref Val	% Rec	LowLirnit	% Rec LowLimit HighLimit RPD Ref Vai	%RPD RPDLimit	Qual
TPHC Diesel (C12-C22) N-Tricosane	34.97 42.5	50 0.10	50.0	. 0	84,9%	70	130 0	Plants.	7

S - Spike Recovery outside accepted recovery limits

ND - Not Detected at the Reporting Limit J - Analyte detected below quantitation limits

Qualifiers:

R - RPD outside accepted recovery limits

Ltd.
oratories,
$\Gamma$ al
Coast ]
North

Date: 24-May-06

Work Order: 06	7 decay and axedy 0604525						***	QC SUMMARY REPORT	IMAR	Y RED	KI
Project: 90	90129701-049/Dutra Trucking	MPCOST - LANGE MARKET - THE STREET			-	***************************************		Lal	boratory	Laboratory Control Spike	Spike
Sample ID LCS-15656	Batch ID: 15656	Test Code;	Test Code: SGTPHDW	Units: µg/L		Analysis	Analysis Date 5/10/06 12:19:41 PM	:19:41 PM	Prep Da	Prep Date 5/7/06	POPPER BOTON STREET
Client ID:		Run ID:	ORGC5_060510A	510A		SeqNo:	591459				
Analyte	Result	Cimit	SPK value	SPK Ref Val	% Rec	% Rec LowLimit	HighLimit RPD Ref Val	Ref Val	%RPD	RPDLimit	Qual
TPHC Diesel (C12-C22) N-Tricosane	204.0	50	50.0	0 .	40.8%	41	96	0	**************************************		
Sample ID LCSD-15656	5 Batch ID: 15656	Test Code:	Test Code: SGTPHDW	Units: µg/L	TOTAL CONTROL TO THE PROPERTY OF THE PROPERTY	Analysis	Analysis Date 5/10/06 12:42:19 PM	:42:19 PM	Prep. Da	Prep. Date 5/7/06	ament overscome property.
Cljent ID;		Run ID:	ORGC5_060510A	510A		SeqNo:	591460			•	
Analyte	Result	Limit	SPK value	SPK Ref Val	% Rec	LowLimit	High Limit RPD	RPD Ref Val	%RPD	RPDLimit	Qual
TPHC Diesel (C12-C22)	193.8	20	200	0	38.8%	41	96	204	5.16%	15	S
N-Tricosane	24.4	0.10	20.0	0	48.7%	38	129	26.3	7.66%	15	
Sample ID LCS-15630	Batch ID: 15630	Test Code: TPHDIW	ТРНБІМ	Units: µg/L	WORND FOR EAST OF FRANCE CONTROL OF THE PROPERTY OF THE PROPER	Analysis	Analysis Date 5/3/06 12:23:52 PM	:3:52 PM	Prep Da	Prep Date <i>5/2/</i> 06	
Client (D:		Run ID:	ORGC7_060503A	503A		SeqNo:	590264				
Analyte	Result	Limit	SPK value	SPK value SPK Ref Val	% Rec	LowLimit	HighLimit RPD Ref Val	RefVal	%RPD	RPDLimit	Qual
TPHC Diesel (C12-C22)	389.3	50	200	0	77.9%	19	120	0	and conference of the conserver of the	-	
N-Tricosane	47.0	0.10	20.0	0	94.0%	70	130	0			
Sample ID: LCSD-15630	) Batch ID: 15630	Test Code: TPHDIW	TPHDIW	Units: µg/L	AN A	Analysis	Analysis Date 5/3/06 12:43:53 PM	(3:53 PM	Prep Dat	Prep Date 5/2/06	фобфиломожения
Client ID:		Run ID:	ORGC7_060503A	503A		SeqNo:	590265				
Analyte	Result	Limit	SPK value	SPK Ref Val	% Rec	LowLimit	HighLimit RPD	RPD Ref Val	%RPD	RPDLimit	Quai
TPHC Diesel (C12-C22)	.405.2	20	200	0	81.0%	29	120	389	4.00%	15	
N-Tricosane	46.2	0.10	50.0	0	92.4%	7.0	130	47.0	1.68%	5	

· B - Analyte detected in the associated Method Blank S - Spike Recovery outside accepted recovery limits R - RPD outside accepted recovery limits ND - Not Detected at the Reporting Limit J - Analyte detected below quantitation limits Qualifiers:

してこれ 13 1

73

3,00

23

3:15

5680 West End Road - Arcata, CA 95521-9202 707-822-4649 - FAX 707-822-6831

# Chain of Custody

LABORATORY NUMBER:	TAT: 024 Hr 048 Hr 05 Day 05-7 Day	PRIOR AUTHORIZATION IS REQUIRED FOR RUSHES	REPORTING REQUIREMENTS: State Forms X Preliminary: FAX □ Verbal □ Rv. / /	Final Report: FAX□ Verbal□ By: / /	3—500 ml pl; 4—1 L Nalgene; 5—250 ml pl;	6—500 ml BG; 7—1 L BG; 8—1 L cg; 9—40 ml VOA; 10—125 ml VOA; 11—4 oz glass jar; 12—8 oz glass jar; 13—brass tube; 14—other	d-Na.S.O.: e-NaOH: f. C. i. O. CH.SO,	2 2 3 3 Collet
	AllVANE	3388 333	PULL TO	7/9	7.7.J	S. (S.) (S.)	(1-1) (-1) (4)	
	Attention: KEN THESSEN Results & Invoice to: WINZGER FRELLY	Address: 633 THIRD ST.	Phone: 707 443 8326. Copies of Report to:	Sampler (Sign & Print):	PROJECT INFORMATION	Project Number: 90129701-049 Project Name: DVTRA TRUCKING	Purchase Order Number:	AB ID SAMPLE ID DATE TIME MATRIX*

	GORN 1 2 COLONS	1307200147			100 C 22 22 ACT					And an annual statement of the statement
		1.	- 1	T -	<del>-</del> -	1	1:	1	_	-
-	-	-	+-	-	-	+	+	+-	<b>├</b> —	1 2
_	-	<del> </del>	├	-	<del> </del>	-	┼	<u> </u>	<del> </del>	╀
	_	┼	├—	_	ļ	<u> </u>	<u> </u>	ļ.,	<u> </u>	L
-			-			_	1	_		L
4		_				_	_	_	_	L
-							_			_
4	-				_					
				1						

E. [1	SHIPPED VIA: UPS Air-Ex Fed-Ex Bus Hand; S=Soil; O=Other.
RECEIVED BY (Sign & Paint) DATE/TIME RECEIVED BY (Sign) DATE/TIME    15.35   1.37.02	*MATRIX: DW=Drinking Water; Eff=Effluent; Inf=Influent; SW=Surface Water; GW=Ground Water; S=Soil; O=Other.

ALL CONTAMINATED NONLACTIFOLIC CARADLEC VALLE DE DETI IDALEN TO

Winzler & Kelly

Fax:7074448330

Jun 8 2006 16:28

P. 19

P.20

#### WINZLER & KELLY CONSULTING ENGINEERS

### STANDARD OPERATING PROCEDURES for MONITORING WELL PURGING AND SAMPLING ACTIVITIES

#### 1.0 OBJECTIVE

To establish accepted procedures for the purging and sampling groundwater from monitoring wells, to ensure that representative samples of formation water are collected by accepted methods.

#### 1.1 Background

To obtain a representative groundwater sample from monitor wells, it is necessary to remove (purge) stagnant water from within and near the well prior to sampling. In general, three to seven casing volumes must be removed from the well prior to sampling, to provide a representative sample. Wells may be sampled after purging less than the minimum three volumes if well recharge rates are beyond reasonable time constraints. The specific method of well purging will be decided on a case by case basis, or as required by project specifications.

#### 1.2 Personnel Required and Responsibilities

<u>Project Manager</u>: The Project Manager (PM) is responsible for ensuring that field personnel have been trained in the use of these procedures and for verifying that monitoring well purging and sampling activities are performed in compliance with these SOP's.

<u>Field Technician</u>: The Field Technician is responsible for complying with these SOP's, including the purging and sampling of monitor wells, the safe containerization of extracted waters, the documentation of field procedures, and the handling of samples..

#### 2.0 WELL PURGING ACTIVITIES

#### 2.1 Equipment Required

- Bottom-filling bailer, suction air pump, air-lift pump, gas operated (bladder) pump, submersible pump, or other pumping device
- pH meter
- Conductivity/Temperature Meter
- Water Level Indicator
- Well Sampling Data Sheet
- Indelible marker
- Disposable gloves
- Containers to hold extracted water (as required)

#### 2.2. Purging Procedure

Prior to groundwater sampling, each monitoring well will be purged as described below. Prior to insertion into each well, all equipment will be either decontaminated (following W&K Decontamination procedures) or will be deemed clean or previously unused by the manufacturer.

- Open all monitoring wells to be purged and allow to equilibrate 5 to 15 minutes.
   Record time and visual observations regarding well access, condition, security, etc. in log book.
- Obtain depth to groundwater level readings according to Winzler & Kelly Standard Operating Procedures for Groundwater Level measurements and Free Phase Hydrocarbon Measurements. Record time and readings on the Well Level Measurement Data Sheet.
- Calculate the volume of standing water in each monitoring well. Record the volume calculated for each well on the Well Sampling Data Sheet.
- Begin purging the well by removing water from the well and collecting in a calibrated container (i.e., 5-gallon bucket marked in 1-gallon increments). The depth, or interval, from which the water is being purged should be noted on the data sheet.
- Obtain readings of field parameters (pH, conductivity, temperature, and turbidity) and make visual observations of color/odor/turbidity at selected intervals (i.e., every gallon, every five gallons, etc.) throughout the purging process. Depending on the calculated volume and the expected number of gallons to be purged, a minimum of five readings should be collected. Record the time, readings, and visual comments on the Purge Data Sheet.
- Continue purging until at least three (minimum) to four well volumes have been removed and the field parameters stabilize to within:

pH  $\approx 0.1$ conductivity  $\approx 10\%$ turbidity  $\approx 10\%$ temperature  $\approx 1^{\circ}$ 

Do not exceed seven well volumes.

- Obtain a final depth to groundwater level measurement prior to collection of the groundwater sample and note the reading and time on the Well Level Measurement Data Sheet. Be sure that the measurement probe has been thoroughly decontaminated prior to insertion into each well. Note any qualitative comments regarding recharge rate of each well, and calculate the percent of the original water column that has recovered at the time of the final depth measurement. It is ideal to attain a minimum of 80% water level recovery prior to sampling, if time constraints allow. Very slow recharge rates may not allow purging the minimum three volumes or 80% recovery; lesser volumes may be used for sampling, as needed and documented.
- Collect a groundwater sample following the directions below under Section 3.0.

• Containerize all purge water and decontamination water in 55-gallon drums. Use yellow indelible markers (storeroom supply) to label all drums on the side with date, contents, origin and other pertinent information. Avoid marking the tops of drums with black marker, such marks are temporary and will soon fade/rust. Note the number, condition and location of drums on site in the field notes.

#### 3.0 WELL SAMPLING ACTIVITIES

#### 3.1 Equipment Required

- Disposable bailer (previously unused) \*
- Bottom emptying device (sampling port)
- Monofilament nylon line (min 40-lb test)
- Monitor Well Purge & Sample Data Sheets
- Sample containers (preserved, as required) provided by the laboratory
- Sample labels
- Indelible marker
- Disposal gloves
- Decontamination soap (Alconox)
- Distilled water for equipment decontamination.
  - \*A variety of sampling techniques are available for the collection of groundwater samples. Except where otherwise required, W&K only utilizes disposable polyethylene bailers to collect groundwater samples.

#### 3.2. Sampling Procedure

Prior to collecting a groundwater sample from a monitoring well, each well must be properly purged in accordance with W&K's SOP for Monitoring Well Purging Activities (See Section 2.0 above), including the measurement of the final water level and documentation of recharge.

- Water from the desired screen interval will be collected by lowering the previously unused disposable, polyethylene, bottom-filling bailer into the well.
- When bailer is completely full, carefully retract the bailer from the well casing.
- Using a previously unused, new, bottom-emptying device, to minimize agitation of the water, transfer the water from the bailer to the sample containers.
- When sampling for volatile constituents (VOA's), the water samples will be collected in 40-ml glass vials (preserved as required by the analyses requested). Precautions will be taken to prevent capturing air bubbles in the vials.
- Upon filling, each vial will be immediately capped with a Teflon septum and plastic screw cap. The vial will be checked for air bubbles by inverting and gently tapping the vial. If any bubbles are visible, the vial will be refilled and confirmed to be free of any air bubbles.

At a minimum, all samples will be labeled with the following information:

Sample ID

Date and Time Sample Collected

Location

Sampler's Initials

Project Number

Analyses Requested

- Sample information will be documented on the Chain-of-Custody form. All samples will be placed in an ice chest, chilled to a temperature of 4°C. The ice chest will remain in the custody of the sampler until it is transferred to the courier service for delivery at the analytical laboratory for analyses. Any and all transfer of sample custody must be documented on the Chain-of-Custody form with the name, signature, affiliation, date and time of the persons releasing and receiving custody of the samples.
- Upon completion of the sampling activities, each well shall be closed and secured by replacing the well cap and securing the lock.
- Dispose of gloves, bailers, bottom-emptying devices, and bailing line after each use.

Winzler & Kelly

Fax:7074448330

Jun 8 2006 16:28

P. 24

#### WATER LEVEL MEASUREMENT DATA SHEET

PROJECT NAME: DOTTRA TYZU CHUNG TODAY'S DATE: 4/26/6 FIELD PERSONNEL: TNIESSCO

WELL	OPEN WELL		L WATER EVEL		WATER	,	TOTAL
NUMBER PRODUCTON	Time	Time	Depth to Water (ft. bgs.)	Time	Depth to Water (ft. bgs.)	COMMENTS	Dept.
lucic !	2:40	3:40	25.7FT		(10, 550.)	TUEFCL 15	<i>^</i> 7
Mus	4:03	4214	20,66			VENTED VIV	02.0
marz	4:08	4215	20.66			7NMPhs 7/26/6	23
MW-3	4:05	4:13	10.54				
Mw-3 Mw-7	3:52	3:59	24.58			MO PROFILM	(5)
MW-5	3:57	4:00	11.17			NO Classiful	C 25
			· ·				25
					*		
						O CONTRACTOR OF THE PARTY OF TH	
			-				
						200	
		CONTRACTOR OF THE PARTY OF THE				O CONTROL OF CONTROL O	
						3.00	
Weath C							
vveatuer Con	ditions Today	7.					
		*					

633 Third Street, Eureka, CA 95501-0417 (707) 443-8326 / FAX (707) 444-8330

Jun 8 2006 16:28

DAVESCOIL Olla-11	
By THIESSON Date 9/27/6 Client	Sheet No of
Subject DUTPA TRUCKING	Job No. 90129701

APPRILE ON- SITE 0930, GATE TO FUEL BUCK PLANT LOCKED. GO TO EDELINE TRUCKING TO GET GATE COMBINATION. ALL WELLS LEXT OP EN OWN NIGHT. BAILER LOFT IN MW-4 TO ATTEMPT SAMPLING 4/27 CUELL MW-1 SAMPLED 4/26/6 WITHOUT PURGING. NO FIELD METERS/AMICYTICAL TOOCS ALWICHBE AT WER

1 MW-4- INADEQUATE GW FOR SAMPLING 4/26 \$4/27

PURGE MW-S DTW=11.17 TD=25 FT WETTED PIPE= 13,23 VOCUME POR CINFT - 0.17 GAL X 13. P3 = 2.35 GAC X 3= (7.05 GA) FINISH PURGING 10:15 AM. WATER TURBIO GAMPLE FOR TPN-D AT 10-300M. WAIT FOR RECHARGE NOTE DURING BAICING OF WELL, DRAW DOWN WAS SUBSTAN TIAC. DTW 10:25=12.7/FT W NO ODOR OR THEEN SAMPLED 2:55P 4/27/6 DTW PRODUCTION WELL = 25.88/10:25A

mw-2 GAGE = 8.75' + D= 20KT WETTED PIPE=16.25' VOL. POR CINET = 0.17GOL X 11.25 = 1.91GAL X 3 = 5.74 GAZ 10:50 COMPLETE PURCING, NO ODOR OR SMEEN

MW-3 GAGE = 10,04' TD=15FT WETTEN PIPE = 4.16' VOL. PLAR CINITY. = 0.17 GAC X 4.16 = 0.7/GAC X 3 (2.12 GAC PINIGH PURGING 11:09 STRONG ORGANIC ODOR